

Genie *SUPERLIFT Contractor* Specifications

Model	SLC-6	SLC-12	SLC-18	SLC-24	
Height-Stowed	86 in 218 cm	86 in 218 cm	86 in 218 cm	86 in 218 cm	
Width	31 ¹ / ₂ in 80 cm	31 ¹ / ₂ in 80 cm	31 ¹ / ₂ in 80 cm	31 ¹ / ₂ in 80 cm	
Width-stabilizers lowered (if equipped)	66 in 168 cm	66 in 168 cm	66 in 168 cm	66 in 168 cm	
Length-Stowed	27 ³ / ₄ in 70 cm	27 ³ / ₄ in 70 cm	27 ³ / ₄ in 70 cm	27 ³ / ₄ in 70 cm	
Length-Operating	54 in 137 cm	58 in 147 cm	68 in 173 cm	76 in 193 cm	
Ground Clearance	2 in 50.8 mm	2 in 50.8 mm	2 in 50.8 mm	2 in 50.8 mm	
Load Capacity at 14" (36 cm) load center	650 lbs 295 kg	650 lbs 295 kg	650 lbs 295 kg	650 lbs 295 kg	
Net Weight	166 lbs 75 kg	204 lbs 93 kg	307 lbs 139 kg	374 lbs 170 kg	
Airborne Noise Emissions by Machinery Maximum sound level at normal operating workstations (A-weighted)	85 dB	85 dB	85 dB	85 dB	
Load Handling Attachments	Length	Width	Depth	Net Weight	
Standard Forks	28 in 71 cm	23 in 59 cm	2 ¹ / ₂ in 6.5 cm	26 ¹ / ₂ lbs 12 kg	
Adjustable Forks	27 ¹ / ₂ in 70 cm	11 ¹ / ₂ to 30 in 29 to 76 cm	2 ¹ / ₂ in 6.5 cm	52 ¹ / ₂ lbs 23.8 kg	
Boom	44 in 112 cm	3 in 8 cm	6 in 16 cm	34 ¹ / ₂ lbs 15.6 kg	
Pipe Cradle	27 ¹ / ₂ in 70 cm	24 ¹ / ₂ in 63 cm	6 in 11.5 cm	10 lbs 4.5 kg	
Load Platform	26 in 66 cm	23 in 58 cm	6 in 15 cm	26 lbs 12.0 kg	
Fork Extensions (each)	30 in 76 cm	2 in 5 cm	3 in 8 cm	4 ¹ / ₂ lbs 2 kg	
Dimensions	SLC-6	SLC-12	SLC-18	SLC-24	
Standard Forks	forks down	5 ft 8 in 1.72 m	11 ft 2 in 3.40 m	16 ft 9 in 5.11 m	22 ft 3 in 6.78 m
	forks up	7 ft 5 in 2.26 m	12 ft 11 in 3.94 m	18 ft 6 in 5.64 m	24 ft 0 in 7.32 m
Adjustable Forks	forks down	5 ft 8 in 1.72 m	11 ft 2 in 3.40 m	16 ft 9 in 5.11 m	22 ft 3 in 6.78 m
	forks up	7 ft 5 in 2.26 m	12 ft 11 in 3.94 m	18 ft 6 in 5.64 m	24 ft 0 in 7.32 m
Boom	6 ft 8 in 2.03 m	12 ft 2 in 3.71 m	17 ft 9 in 5.41 m	23 ft 3 in 7.09 m	